



DESCRIBE CORNER MONUMENT FOUND
 Found 2" diameter Iron Pipe with pipe cap, marked appropriately, accepted as set by proper methods.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
 None

PHOTO IDENTIFICATION DATA
 Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
 Signature _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
 From Madera Co. Road 221 and the PGE flume, the corner is approximately 400' east in a E-W fence.

PLANE COORDINATE POSITION DATA
 State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
 Agency _____

Signature M. R. Seaman Title LS 5339 Division _____ Headquarters _____ Date 4/19/95 FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT
 Found 2" diameter Iron Pipe with pipe cap marked:
 T8S R22E
 S2 1/4
 S11
 LS 1969

- ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE
1. A 25" diameter Ponderosa Pine, blazed and scribed, "NBT" bears S75°32'W, 36.20'.
 2. A 12" diameter White Oak, blazed and scribed "NBT" bears S39°40'W, 69.12'.
 3. A 26" diameter White Oak, blazed and scribed "NBT" bears S14°56'E, 94.51'.
 4. Set metal post with USFS signs bears S45°E, 4'.

Work Done By R. Seaman Title L.S. Date 4/13/95 State Registration No. 5339 or Agency _____
 Certified Cor. Record Prepared? Yes No Filed At. _____ Date _____

REMARKS
 Bearings are to the center of the trees, distances are horizontal to a nail and tag LS 5339 driven into the side center of the root crown. Posted USFS monument and bearing tree signs as required.